DEFENSE





US Army Corps of Engineers & Washington Headquarters Services

"Turning a DoD GOLD Leaf" BRAC 133 @ Mark Center

Joanne Hensley, USACE Crystall Merlino, LEED AP, WHS

E2S2 Symposium & Exhibition, June 14-17, 2010

a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified	Same as Report (SAR)	24	
16. SECURITY CLASSIFIC			17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON
15. SUBJECT TERMS					
14. ABSTRACT					
13. SUPPLEMENTARY NO Presented at the Ni held 14-17 June 20	DIA Environment, I	Energy Security &	Sustainability (E2	S2) Symposi	um & Exhibition
12. DISTRIBUTION/AVAIL Approved for publ	LABILITY STATEMENT ic release; distributi	on unlimited			
				11. SPONSOR/M NUMBER(S)	IONITOR'S REPORT
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)			10. SPONSOR/MONITOR'S ACRONYM(S)		
	ZATION NAME(S) AND AD of Engineers ,441 G S	` /		8. PERFORMING REPORT NUMB	G ORGANIZATION ER
				5f. WORK UNIT NUMBER	
			5e. TASK NUMBER		
6. AUTHOR(S)				5d. PROJECT NU	JMBER
				5c. PROGRAM E	ELEMENT NUMBER
4. TITLE AND SUBTITLE 'Turning a DoD G	OLD Leaf' BRAC 1	33 @ Mark Center	•	5a. CONTRACT 5b. GRANT NUM	
1. REPORT DATE JUN 2010		2. REPORT TYPE			0 to 00-00-2010
maintaining the data needed, and c including suggestions for reducing	election of information is estimated to completing and reviewing the collection this burden, to Washington Headquuld be aware that notwithstanding and OMB control number.	ion of information. Send comment arters Services, Directorate for Inf	s regarding this burden estimate formation Operations and Reports	or any other aspect of the property of the contract of the con	his collection of information, Highway, Suite 1204, Arlington

Report Documentation Page

Form Approved OMB No. 0704-0188





BRAC 133 at Mark Center "Turning a DoD GOLD Leaf"

Overview

Background of project and team

- Moving the project from Silver to Gold
 - Integrated approach
 - Review of LEED scorecard

Quality Assurance to keep us on track





- Base Realignment and Closure
- In 2005, the BRAC process mandated the move of many DoD offices from leased office space to secure sites that could meet DoD's high anti-terrorism security standards.







- BRAC-133 at Mark Center facility will be a new office complex in Alexandria, VA designed to house over 6,400 Department of Defense personnel
- 1.8 million square feet of world class office space
- Expected turnover September 2011
- Project is being designed and constructed to achieve a U.S. Green Building Council, Leadership in Energy and Environmental Design (LEED), New Construction "GOLD" level-rating







Government Team

- U.S. Army's Fort Belvoir, VA
- US Army Corps of Engineers
- Washington Headquarters Services


Contracting Team

- Duke Realty Corporation
- Clark Construction
- HKS Inc.
- Studios Architecture
- Wisnewski Blair & Associates

^{*}other teaming partners











- The BRAC 133 project will be built on 16 acre site in Mark Center
- Two vertical office towers
- Two parking structures
- Visitor's Center
- Publicly accessible community
 Transportation Center











- Sustainability integrated into request for proposal. Stated mandatory USGBC LEED "Silver" level-rating
- Team easily demonstrated Silver level achievable through design proposed.
- By implementing cutting-edge strategies in environmentally sustainable construction and site development the team ensured the highest levels of water savings, energy efficiency, indoor environmental quality, and sustainable site design – the team would be able to achieve GOLD





Sustainability goals:

It is anticipated that the building will consume 30% less energy than a traditional building of the same size.

- Energy Efficiency features include:
 - High Efficiency Central Chiller Plant
 - Demand Controlled Ventilation
 - Energy efficient lighting, including LED fixtures and Occupancy Sensors
 - Dedicated Outdoor Air System with Energy Recovery Wheels





Sustainability goals:

It is anticipated that the building will use 45% less water than a traditional building of the same size—a savings of 4.5 million gallons annually.

- Water saving strategies include:
 - Low flow faucets, shower heads, and plumbing fixtures
 - Zero irrigation and drought tolerant landscaping






Sustainability goals:

- At the current pace, 6 million pounds of construction waste will be recycled during the 3 year building project. This waste would typically go to a landfill on a non-LEED project.
- BRAC 133 will include it's own Transportation Center to encourage use of mass transit such as busses and shuttle services. Onsite parking is limited to 60% of the overall occupants, and 375 preferred parking spots are allocated for carpools and hybrid vehicles. Amenities are also provided for bicycle commuting.
- The project design also maximizes the use of visible green elements, including green roof designs for the Visitor's Center and Remote Inspection Facility, a bioswale for filtering stormwater runoff, and a green screen that wraps the façade of one parking structure.







Environment, Energy Security and Sustainability Symposium & Exhibition







BRAC 133 Department of Defense · WHS · Mark Center

NORTH PARKING STRUCTURE VIEW RENDERINGS

A0-09B R1
















BRAC 133 Department of Defense · WHS · Mark Center

TOWER NORTH APPROACH VIEW RENDERING

A0-04B R1

















BRAC 133 Department of Defense · WHS · Mark Center

NORTH PARKING & TRANSPORTATION CENTER RENDERING

A0-09A R1 October 19, 2009













Sustainable Sites	
Prerequisite 1: Erosion & Sediment Control	Y
Credit 1: Site Selection	
Credit 2: Urban Redevelopment/Development Density	1
Credit 3: Brownfield Redevelopment	
Credit 4.1: Alternative Transportation: Public Transportation Access	1
Credit 4.2: Alternative Transportation: Bicycle Storage & Changing Rooms	1
Credit 4.3: Alternative Transportation: Alternative Fuel Refuel station	1
Credit 4.4: Alternative Transportation: Parking Capacity	1
Credit 5.1: Reduced Site Disturbance: Protect or Restore Open Space	
Credit 5.2: Reduced Site Disturbance: Development Footprint	1
Credit 6.1: Stormwater Management: Rate & Quantity	
Credit 6.2: Stormwater Management: Treatment	
Credit 7.1: Landscape & Exterior Design to Reduce Heat Islands: Non-roof	1
Credit 7.2: Landscape & Exterior Design to Reduce Heat Islands: Roof	1
Credit 8: Light Pollution Reduction	
Points Achieved:	8





Water Efficiency	
Credit 1.1: Water Efficient Landscaping: Reduce by 50%	1
Credit 2.1: Water Efficient Landscaping: Non potable use or no irrigation	1
Credit 2: Innovative Wastewater Technologies	1
Credit 3.1: Water Use Reduction: 20% Reduction	1
Credit 3.2: Water Use Reduction: 30% Reduction	
Points Achieved:	4





Energy & Atmosphere	
Prerequisite 1: Fundamental Building Systems Commissioning	Y
Prerequisite 2: Minimum Energy Performance	Y
Prerequisite 3: CFC Reduction in HVAC&R Equipment	Y
Credit 1.1: Optimizing Energy Performance: 20% New/10% Existing	2
Credit 1.1: Optimizing Energy Performance: 20% New/10% Existing	1
Credit 1.1: Optimizing Energy Performance: 20% New/10% Existing	1
Credit 1.1: Optimizing Energy Performance: 20% New/10% Existing	1
Credit 1.1: Optimizing Energy Performance: 20% New/10% Existing	
Credit 2.1: Renewable Energy: 5%	
Credit 2.2: Renewable Energy: 10%	
Credit 2.3: Renewable Energy: 20%	
Credit 3: Additional Commissioning	1
Credit 4: Ozone Depletion	1
Credit 5: Measurement & Verification	1
Credit 6: Green Power	
Points Achieved:	8





Materials & Resources	
Prerequisite 1: Storage & Collections of Recyclables	Y
Credit 1.1: Building Reuse: Maintain 75% of Existing Shell	
Credit 1.2: Building Reuse: Maintain 100% of Existing Shell	
Credit 1.3: Building Reuse: Maintain 100% Shell & 50% Non-shell	
Credit 2.1: Construction Waste Management: Divert 50%	1
Credit 2.2: Construction Waste Management: Divert 75%	1
Credit 3.1: Resource Reuse: Specify 5%	
Credit 3.2: Resource Reuse: Specify 10%	
Credit 4.1: Recycled Content: 10%	1
Credit 4.2: Recycled Content: 20%	1
Credit 5.1: Local/Regional Materials: 20% Manufactured Locally	1
Credit 5.2: Local/Regional Materials: of 20% above, 50% Harvested Locally	1
Credit 6: Rapidly Renewable Materials	
Credit 7: Certified Wood	1
Points Achieved:	7





Indoor Environmental Quality	
Prerequisite 1: Minimum Indoor Air Quality (IAQ) Performance	Y
Prerequisite 2: Environmental Tobacco Smoke (ETS) Control	Y
Credit 1: Carbon Dioxide (CO2) monitoring	1
Credit 2: Increase Ventilation Effectiveness	1
Credit 3.1: Construction IAQ Management Plan: During Construction	1
Credit 3.2: Construction IAQ Management Plan: Before Occupancy	1
Credit 4.1: Low-Emitting Materials: Adhesives & Sealants	1
Credit 4.2: Low-Emitting Materials: Paints	1
Credit 4.3: Low-Emitting Materials: Carpet	1
Credit 4.4: Low-Emitting Materials: Composite Wood	1
Credit 5: Indoor Chemical & Pollutant Source Control	
Credit 6.1: Controllability of Systems: Perimeter	1
Credit 6.2: Controllability of Systems: Non-Perimeter	
Credit 7.1: Thermal Comfort: Comply with ASHRAE 55-1962	1
Credit 7.2: Thermal Comfort: Permanent Monitoring System	1
Credit 8.1: Daylight & Views: Daylight 75% of spaces	
Credit 8.2: Daylight & Views: Views for 90% of spaces	
Points Achieved:	11





Innovative & Design Process	
ID Green Education	1
ID Green Cleaning	1
ID Recycled Content 30%	1
ID Local Materials 30%	1
ID Construction Waste Management >75%	
ID HVAC Innovations	
Credit 2: LEED Accredited Professional	1
Points Achieved:	5

TOTAL Project points:	43
-----------------------	----

LEED Certified = 26-32 points

LEED Silver = 33-38 points

LEED Gold = 39-51 points

LEED Platinum = 52 or more points





Sustainability & Team Management

- Contract requirements upheld and surpassed
- ✓ Specifications integrated sustainability and LEED requirements
- ✓ Full team integration achieved
- ✓ Weekly Design meetings sustainability discussed
- ✓ Semi-monthly LEED review meetings full team participation
- ✓ Constant monitoring





In conclusion...

- ✓ LEED ongoing design submission in review
- ✓ Sustainability and team integration key to success
- ✓ High Performing building for new tenants